

# Design and Construction of the John James Audubon Bridge

SASHTO ANNUAL CONFERENCE, New Orleans, LA  
August 25, 2014

Paul Fossier, P.E., F.ASCE, Bridge Design Engineer Administrator




# LOUISIANA BRIDGE INVENTORY

## (2013 FHWA National Bridge Inventory Data)

- **13,050 LA. BRIDGES (607,751 in U.S.)**
  - 8,087 ON SYSTEM (STATE)
  - 4,963 OFF SYSTEM (NON-STATE)
  - **1<sup>st</sup> in US** -151 ARE MOVABLE (Lift, Swing, Bascule, Pontoon) BRIDGES
  - 12 Miss. River Crossings (10 Truss, 2 Cable Stay)
  - **21<sup>th</sup> in US**, NUMBER OF BRIDGES
  - **4<sup>th</sup> in US**, BRIDGE AREA (Length x Width)


**ALTERNATE ALIGNMENTS  
DURING ENVIORNMENTAL  
PHASE**



**US 61**


**SELECTED ALIGNMENT**

# Project Scope



- ★ Total Cost \$406 Million, LA “TIMED” PROGRAM, 4 cent gas tax, sold bonds
- ★ Project Length 15.3 miles
- ★ Bridge Length: 4.0 miles (main bridge & main bridge approach 4 lanes, other bridges 2 lanes)
- ★ Roadway 11.3 miles (2 lane, buy R/W for future 4 lane)
- ★ First Design-Build Procurement for LA DOTD
- ★ Successful Letting March 2, 2006, Start construction May, 2006.
- ★ Opened to traffic on May 5, 2011, Other misc. work and punch list items not completed till February 2012


# The Bridges



# **BRIDGE PROJECT FEATURES**

- **Cable Stayed Superstructure Main Span:**
  - 1583 ft. longest stay cable span in Western Hemisphere when completed.
  - Galvanized and sheathed 7 wire prestressed strands and outer HDPE pipe (multi levels of protection)
  - Steel edge girders, steel floor beams, weathering unpainted steel.
  - Precast concrete panels with latex concrete overlay
  - Concrete cast-in-place towers. Lock up device at one towers.
  - Wind Analysis with computer simulation and wind tunnel, Wind faring plate used on main span
- **Main Span River Piers:**
  - Unique cofferdam for low water footing, first on Miss. River with drilled shafts. Designed for vessel /barge impact loads.
  - Tip grouted 8' dia. drilled shafts in river, Construction Techniques- Oscillated and Fully Cased
  - O(Osterburg) - Cell load testing to verify shaft load capacities

# Cable-Stayed Main River Span




**1583 ft main span, 1463 ft navigational clearance**

**Main span  
substructure**





# Tower Foundations 1W & 1E

- 160' x 64' x 18' Cap
- 7 by 3 drilled shaft group
- 8'-0" diameter shafts - 21 per each pier




# Tower Shafts

- 96" dia permanent casing
- 90" dia drilled shaft
- Pile tip Elev. -175 to -180
- Tip grouting



# Footing Cofferdam Structure Sequence

Piles and  
trestle have  
been  
installed



# Shaft Template






# Drive Permanent Casing

- Vibratory hammer driving the casing into the ground

# Drive Temporary Casing

- Temporary casing is driven inside the permanent casing with an Oscillator






# Excavate Temporary Casing – Hammer Grab or Air Lifts



West - 175



Bottom of Permanent Casing

90'' Temporary Casing

Hammer Grabs

East - 180


# Excavation by Air Lifts







# Base grouting verification

- Pressure
- Volume
- Movement of Shaft






# Install Soffit Panels





# Install Bracing Frame

- Install first tier of brace frame






12/10/2008


# Erect Pre-Cast Wall

- Install pre-cast walls
- Connect to soffit panels and first tier brace frame



# Install Jacking System

- Install jacking system with permanent hangers
- Lower structure to facilitate 2<sup>nd</sup> & 3<sup>rd</sup> tier bracing installation






12/16/2008 12:32

# Install Additional Brace Frames

- Install 2<sup>nd</sup> and 3<sup>rd</sup> tier brace frame.




# Cofferdam Structure with Bracing



# Install Follower Sheeting


- Install sheet pile





# Lower Structure

- Lower structure to final elevation
- Lock off hangers




January 11,  
2009




# Pour Concrete Seal

- Install 8 foot concrete seal



# Remove Hangers and Cut Casing


- Remove hangers
- Cut casing






# Place Reinforced Pile Cap

- Place reinforced pile cap concrete




# Place Pedestal Concrete

- Remove center section of level 2 strut
- Place pedestal reinforcing and concrete lift 1
- Restrut as required
- Remove center section of level 1 strut



# Remove Cofferdam


- Remove sheeting
- Remove Bracing
- Patch blockouts







# Tower Cross Section



- Anchor box sections for simple jump forming
- Cable anchorage inside tower wall
- Elevator in each leg

# Tower and Cross-Beam Forms



Main span  
Superstructure

# Stage-by-Stage Analysis

- Structure built one segment at a time
- Precisely captures locked-in effects
- Models time-dependent effects during construction
- Required for tracking bridge geometry during construction
- Performed prior to bridge construction

# Construct pier table




April 4, 2010

Pier Table Erection




# Bridge Construction




June 9, 2010

Simultaneous tower  
and superstructure  
erection



# Bridge Construction



November 7, 2010

Completion of  
Backspan and Transition Span




December 12,  
2010






12/29/2010

# Composite Deck Cross-Section



- Economy, simplicity and constructability
- Durability
- Accessibility
- Low maintenance

# Composite Deck Cross-Section





12/28/2010

# Stay System



- 7-Wire parallel strand
- Monostrand Jacking
- State-of-the-Art Corrosion Protection
  - Galvanizing
  - Grease
  - Strand PE
  - Coextruded HDPE Pipe
- Vibration suppression
- Anti-Vandalism end pipe
















Joint Venture of:

- Granite Construction
- Flatiron Construction
- Parsons Transportation Group



**LTM – LOUISIANA TIMED MANAGERS – PB, GEC, LPA Group**  
**Main Span EOR: Buckland Taylor & Parsons Transportation**  
**LA DOTD Project Manager - DOTD Bridge Design Section**